BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Yelahanka Zone, Bruhath Bengaluru Mahanagara Palike.

Tender Notification No: EE/ELE/YZ/TN/GN/04 /2012-13 Date: 28-08-2012

Item No. 24

SCHEDULE - B

Name of Work: Providing and Fixing of Street lights and other street lighting accessoriesin Ward No-10

Name of the Firm				Sri narasimha prassana electricals		
Sl no	Approved Qty	Description	Unit	In Figures	In Words	Amount
1	5	Supplying High pressure sodium vapour street light fitting die cast aluminium canopy with aluminium housing for control gear, finished stove enamel gray glassy white canopy interior with a pair of anodized aluminium reflectors with toughened flat glass, gasket lining for drip insect resistance duly wired with porcelain holder copper choke, igniter and HPF condenser including a sodium vapour lamp. II 250 Watts a) Group 'A'	Each	6150.00	Rupees Six thousand one hundred and fifty only	30750.00
2	5	Supplying & fixing mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. b) Using 32mm dia G.I pipe	Each	685.00	Rupees Six hundred and eighty five only	3425.00
3	15	Supply and fixing of ..... cross arm including all Hardwares compete as per the standard technical specification. b) 2 Pin 45x45x5mm-510mm	Each	123.00	Rupees One hundred and twenty three only	1845.00
4	30	Supplying and Fixing..... including all Hardwares etc complete as per the Standard technical Specification. a) 1.1 KV Pin insulator	Each	70.00	Rupees Seventy only	2100.00
5	500	Supplying and stringing of ACSR Conductor (6/2.59mm Al+1/2.59mm steel)	Mtr	19.80	Rupees Ninteen and eighty paise only	9900.00
6	15	Supplying and fixing ..... including all Hardwares etc complete as per the standard technical specification e) RCC Clamp	Each	61.00	Rupees Sixty one only	915.00
7	22500	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer pain and finally finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete b) 16 SWG	sqcm	0.33	RupeesTthirty three paise only	7425.00
8	3	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete c) 63 Amps	Each	219.00	Rupees Two hundred and ninteen only	657.00
9	3	Supplying and fixing Microprocessor based Astronomical timer switch with using necessary bolts, nuts and washers etc.,	Each	7515.00	Rupees Seven thousand five hundred and fifteen only	22545.00

10	3	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and Complete wiring as required. b) 40-63 Amps SP 1) Group 'A'	Each	370.00	Rupees Three hundred and seventy only	1110.00
11	3	Supply and fixing of 4 pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947. c) 60-70 Amps	Each	3865.00	Rupees Three thousand eight hundred and sixty five only	11595.00
12	6	Supplying and fixing angle iron frame work fabricated out of M.S angle iron... and M.S. flat... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint. . (32.9a) a) 40x40x6mm	Rmtr	240.00	Rupees Two hundred and forty only	1440.00
13	35	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Classl. Class 'A' PVC Cable d) 4 core 16sqmm	per mtr	150.00	Rupees One hundred and fifty only	5250.00
14	35	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required.II. On wall /Structure a) 6 sqmm to 16sqmm	Rmtr	18.00	Rupees Eighteen only	630.00
15	24	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 16 sqmm	Each	14.00	Rupees Forteen only	336.00

Percentage

In Figures	**7% Above**	**ABOVE**
In Words	**Seven percent Above**	**ABOVE**

I am prepared to take up the above work at --------% above/below (In Words ----------) the rates quoted in the Schedule 'B'

Signature of the Contractor

Executive Engineer (Ele)
Yelahanka Zone BBMP